



ROAD MARKING KEY:

Dia No.	Marking	Details
1003A		Double intermittent line, 600mm line, 300mm gap, 200mm wide.
1004		Intermittent line, 4000mm line, 2000mm gap, 100mm wide.
1009A		Intermittent line, 600mm line, 300mm gap, 100mm wide.
1062		Road Hump. 750mm wide, variable length.
1018.1		Double yellow line, 50mm wide.

Notes:

- Ordnance survey details shown coloured grey; do not scale from OS details.
- Existing surveyed details are shown coloured green.
- Contractor will need to liaise with occupiers of the properties adjacent to the works prior to carrying out any works that may affect their property.
- This drawing is to be read in conjunction with all other drawings, specification and other related information.
- Proposed kerb upstand to match existing at tie-ins.

Site Risks:

- BT overheads in these locations. Contractor to carry out overhead proximity survey prior to start of works
- UKPN electricity covers. Do not touch. To be adjusted by UKPN operative only.

Key:

- New precast concrete HB2 kerb. For kerb details please see NCC standard dwg NCD-1100-02.
- New precast concrete Edging. For kerb details refer to NCC standard dwg NCD-1100-02. Note: Terminate edging in front of residential driveway & gates
- New precast concrete 125x255mm BN kerb with 25mm upstand. For kerb details please see NCC standard dwg NCD-1100-02.
- Edge of existing carriageway.
- Proposed carriageway full depth construction. Refer to PDC1 in the appendix 7/1.
- Proposed raised table. Refer to NCD 1100-15.
- Footway Reconstruction (Pedestrian Loading) to be flush with raised table.
- Footway Resurfacing (Pedestrian Loading) to be flush with raised table.
- Footway Resurfacing (Domestic Vehicular Loading) to be flush with raised table.
- New buff coloured blister tactile paving of 400'400'50mm. For tactile details refer to NCC standard dwg NCD-1100-19. Stick on required for section of BT cover within tactile on Marion Road.
- Proposed gully with connecting pipe of 150mm dia.
- Existing Utility covers to be readjusted to proposed level.
- Existing drainage covers to be readjusted to proposed level.



Grahame Bygrave
 Executive Director of
 Community and Environmental Services
 Norfolk County Council
 County Hall, Martineau Lane
 Norwich NR1 2SG

DRAWING TITLE
 PMB673 BEATRICE ROAD
 GENERAL ARRANGEMENT PLAN
 SHEET 1 OF 2

REV.	DESCRIPTION	CHECKED	DATE
C01	CONSTRUCTION ISSUE	SD	MAY-26

INITIALS	DATE	DRAWING No.
KI	MAY-26	PMB673-000-0100-001
PU	MAY-26	PROJECT TITLE
PD	MAY-26	PMB673 BEATRICE, FLORENCE, & MARION ROAD RAISED TABLE
SD	MAY-26	SCALE
		1:200 @ A1
		FILE No.
		PMB673